



Show room (3 rooms +kk) module installation in Tampere, Finland

Insights into YIT's global research and practises on productivity

MARKO OINAS, INTERIM EVP, M.SC.

YIT, HOUSING FI & CEE

PRODUKTIVITĀTE BŪVNIECĪBĀ 3RD DEC 2020

We are the largest Finnish and a significant North European construction and development company

Finland

Revenue ~2,500
Personnel ~4,300



Scandinavia

Revenue ~150
Personnel ~200



Russia

Revenue ~300
Personnel ~1,300



Baltic countries

Revenue ~300
Personnel ~1,200



CEE countries

Revenue ~100
Personnel ~300



Restated revenue by geography, EUR million 2019



Revenue

3.4


EUR billion in 2019

Adjusted operating profit

166

EUR million in 2019

Revenue by segment




On July 4, 2019, YIT announced the sale of its Nordic paving and mineral aggregates businesses. The transaction is estimated to be completed during the first or the second quarter of 2020. Figures refer to continuing operations.

YIT announced on July 4, 2019 the sale of its Nordic paving and mineral aggregate businesses.

YIT

Likelihood of change in construction business and impacts



Global study of industrialized housing construction companies



Volumetric modules

(80-95% ready off-site)



Panels

(60% ready off-site)

Product structure

Frame material


Concrete

Steel

Wood

	Concrete	Steel	Wood
Volumetric modules			
Panels			

Shorter lead time when site works are done parallel with the works in factory



Prefabrication steps in YIT housing

Enablers / Results

1970

Development of concrete elements in Finland

BES (BetoniElementti-Standardi). Industry wide open system with standard measures. (Finnish specialty)



1985

YIT's wood panel factory in Hämeenlinna

Profitable success in standardised bungalows for YIT's Hämeenlinna unit.



1997

Developer based apartments for consumers


Design management expertise and sales. Product development evolution in unit level.



2015

Centralized product development

9000 bathroom pods over the years.



2019

BIM and volumetric modules

- *BIM in every project*
- *1st Module pilot*



YIT's experiences with bathroom pods

Decreasing the amount of work on-site

- Approximately 50% of the apartments interior work comes with the one lift
- Most of the technical instruments are installed in the factory
- Work safety point of view (less work on-site)

Shortening the construction time

- Bathroom pods shorten the construction time by 2 months

Quality and functionality


- Fine tuned functionality and large procurement volume
- Work is done in series, in warm, dry and well-lit environment
- YIT has built already more than 8000 homes with bathroom pods



YIT's own bathroom pod catalogue: Fine tuning features with prototypes



Hollow core slabs in place before the joints and bathrooms



Sealed bathroom pods being installed to the building frame



YIT's volumetric module pilot: Tampereen Tohtori

- Designed for rental purposes. 63 apartments (1 and 3 rooms apartments)
- Construction time 4kk. Module assembly in week 9 2020.



- Module installation took less than a week: From Tuesday to Sunday
- Installation took 20 min per module.

20°

30°

40°

50°



Lean and Takt time production

Lean principles


- Identify and remove “waste” (unnecessary activities)
- Improve the flow of work and material

Dividing work and spaces to smaller parts


- Half a day specific planning instead of week
- Half of an apartment instead of whole floor
- Right resources and materials in right place at the right time

Takt time driven logistics supporting

- No extra material in the floor levels



1. **BIM** ➡ From theory in to practice
2. **Better preplanning** ➡ Optimising work and site
3. **Takt time production** ➡ Shortened construction time
4. **Prefabrication** ➡ Improved speed and quality



**Together
we can
do it.**